



PAT CHECKBOX

PRODUCT PROFILE

The PAT Checkbox has been designed to provide a safe, simple and quick means of checking the calibration of the Seaward PATs, to ensure accurate testing. The Checkbox will also check other Portable Appliance Testers - it is calibrated with a flash voltage of 3kV rms and an insulation resistance test voltage of 500V DC.



Product Specification

Earth Bond Reading	+/- 1%	+/- 1 digit
Insulation Reading	+/- 1%	+/- 1 digit
Flash Test Reading	+/- 1%	+/- 1 digit
Earth Leakage Reading	+/- 1%	+/- 1 digit